

R

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

DEC 14 1964

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Western Petroleum Co., Inc. 15-047-16128-0000

Complete Address: Box 65, Great Bend, Kansas

Lease Name Donovan Well No. # 1

Location SW NW Sec. 24 Twp. 26 Rge. 18 (E) (W) W

County Edwards Total Depth 4795

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Western Petroleum Co., Inc.

Address: Box 65, Great Bend, Kansas License No.

Operation Completed: Hour 10:00AM Day 10th Month Dec. Year 1964

The Above well was plugged as follows:

335' of 8 5/8" surface pipe, cement circulated with 300 sacks. Fluid
was up in the hole. 1st cementing plug and 1/2 sack of hulls was pushed
in fluid to 300', and cemented with 25 sacks, through the drill pipe.
Hole was filled with drilling mud to 40', 2nd cementing plug, bridged
solid with hulls on fluid at 40', and cemented with 10 sacks to the
base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12-14-64

INV. NO. 333-W

Signed: Archie Elving
Well Plugging Supervisor