

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 047- 20,685-0000 (of this well)

Operator's Full Name F & M Oil Co., Inc.

Complete Address 422 Union Center, Wichita, Ks. 67202

Lease Name Neff Well No. 1

Location C SE SW Sec. 26 Twp. 25 Rge. 18 (E) (W) X

County Edwards Total Depth 4690

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Mustang Drilling Co.

Address Box 1425, Great Bend, Ks. 67530 License No.

Operation Completed: Hour 1 Am. Day 8 Month 6 Year 1980.

The above well was plugged as follows:

326' 8 5/8" casing w/250 sax cement. Set 40 sax cement plug at 600'-
Set 40 sax cement plug at 330'-Bridge at 40' & 10 sax cement to 5'
below Gl. 5 sax in rat hole & 2 sax in water well. Cemented by Allied.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 6-11-80

INV. NO. 2328w

RECEIVED
6-11-80
JUN 11 1980

DRILLERS WELL LOG

DATE COMMENCED: May 30, 1980
 DATE COMPLETED: June 9, 1980

F & M Oil Co., Inc.
 NEFF # 1
 C SE SW
 Sec 26-T25S-R18W
 Edwards Co., Kansas

0 - 200' Surface Clay, Sand
 200 - 343' Shale
 343 - 1270' Red Bed, Shale
 1270 - 1286' Shale
 1286 - 1304' Anhydrite
 1304 - 1900' Shale
 1900 - 2880' Shale and Lime
 2880 - 4050' Lime and Shale
 4050 - 4192' Shale and Lime
 4192 - 4298' Lime and Shale
 4298 - 4415' Shale and Lime
 4415 - 4515' Lime
 4515 - 4690' Lime and Shale
 4690' RTD

SAMPLE TOPS

Anhydrite 1286
 Base Anhydrite 1304
 Heebner 3936
 Toronto 3953
 Lansing 4079
 Mississippi 4622
 RTD 4690

SURFACE PIPE:
 Set new 8 5/8", 23# pipe
 at 326' w/225 sacks Common
 2% Gel, 3% cc.

A F F I D A V I T

STATE OF KANSAS)
 COUNTY OF BARTON) ss.

I, Milford Martin, of the Mustang Drilling, Inc. state that I have knowledge of the facts, statements and matters herein contained and that the same are true and correct.

Milford Martin

Subscribed and sworn to before me this 11th day of June, 1980.

Beverly Shewbart

 Notary Public

STATE NOTARY PUBLIC
 BEVERLY SHEWBART
 Barton County, Kansas

My Commission Expires: April 14, 1982

RECEIVED
 STATE CORPORATION COMMISSION

JUN 12 1980

CONSERVATION DIVISION
 Wichita, Kansas