

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 4 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Northern Pump Co. 15-047-30063-0000

Complete Address Box 937 Garden City, Ks

Lease Name McClanahan-Ellinghaus Well No. 1

Location C NW/NE Sec. 26 Twp. 26 Rge. 18 (E) (W) W

County Edwards Total Depth 3283

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Knight Casing Pulling Co.

Address Box 405 Chase, Ks License No. 436

Operation Completed: Hour 12:30 PM Day 2 Month 11 Year 1970

The above well was plugged as follows:  
289 ft. of 8 5/8 surface pipe circulated.  
452 ft of 7" surface pipe circulated. 3282 ft of 4 1/2 long string  
cemented with 150 sacks. Top perf. 3238 ft. Sand back to 3200.  
4 sacks cement with bailer. Pulled 2450 ft of 4 1/2. Set 10 ft rock  
bridge at 340 ft. Fill hole with 5 yds. of redimix to base of  
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 11/4/70

INV. NO. 2804-U