

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-047-00772-0000

RECEIVED  
STATE CORPORATION COMMISSION

DEC 19 1963

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Kenneth Rupp Oil Producer

Complete Address: 1035 Wichita Plaza, Wichita, Kansas

Lease Name O'Conner-Gamble Unit # 1 Well No. # 1

Location C SE NW Sec. 29 Twp. 26 Rge. 18 (E) (W) W

County Edwards Total Depth 4811

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Red Tiger Drilling Co.

Address: 1720 Wichita Plaza, Wichita, Kansas License No. \_\_\_\_\_

Operation Completed: Hour 12:00PM Day 18th Month December Year 1963

The Above well was plugged as follows:

281' of 8 5/8" surface pipe, cemented with 200 sacks. Fluid level was  
up in hole. 1st cementing plug and 1/2 sack hulls was pushed to 275',  
cemented, through the drill pipe, with 25 sacks. Hole was filled with  
drilling mud to 40', 2nd cementing plug, bridged with hulls, cemented  
10 sacks to base cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12/19/63

INV. NO. 8315-W

Signed: Archie Elving  
Well Plugging Supervisor