

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 22 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Messman-Rinehart Oil Company 15-647-00034-0004

Complete Address: 1432 Wichita Plaza Bldg., Wichita, Kansas

Lease Name Sturgeon Well No. # 1

Location SE SE NW Sec. 33 Twp. 26 Rge. 18 (E) (W) W

County Edwards Total Depth 4881

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Flint Engineering & Construction Company

Address: Box 950, El Dorado, Kansas License No. 547

Operation Completed: Hour 2:30PM Day 21st Month Dec. Year 1964

The Above well was plugged as follows:

320' of 8 5/8" surface pipe, cement circulated. 4881' of 5 1/2" long string,
cemented with 75 sacks. Plug back to 4272'. Top perforation 4243'. Bottom
of the hole was sanded to 4240', and cemented with 5 sacks. Fluid level in
the hole was at 80'. Bridge plug was pushed in fluid to 300', and 15' of
rock bridge. 1 sack of Cal-Seal was mixed in barrel and put on plug at 285',
through the dump bailer. And let set for 2 hours. Hole was bailed dry, and
25 sacks of cement added to plug. Hole was filled with mud to 40', and 10'
of rock bridge, and cemented with 10 sacks to the base of the cellar. 2800'
of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 12/23/64

INV. NO. 388-11