

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 28 1966
7-28-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Rupe-Stoskopf

Complete Address: 222 Brown Bldg., Wichita, Kansas

Lease Name A. O. Derley Well No. # 1

Location C NE SW Sec. 36 Twp. 25 Rge. 18 (E) (W) W

County Edwards Total Depth 4671'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Leben Drilling, Inc.

Address: 815 Wichita Plaza Bldg., Wichita, Kansas License No.

Operation Completed: Hour 11:00AM Day 26th Month July Year 1966

The Above well was plugged as follows:

. 274' of 8 5/8" surface pipe, cement circulated with 225 sacks. Fluid
level in the hole was at 100'. 1st cementing plug and 1/4 sack of hulls
was pushed in fluid to 250', and cemented with 25 sacks, through the
drill pipe. Hole was filled with drilling mud to 40', 2nd cementing
plug, bridged with 1 sack of dry cement and 1/2 sack of hulls on fluid
at 40', and cemented with 9 sacks to the base of the cellar. Rat hole
bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 7/28/66
INV. NO. 3639-44