

16
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
MAY 20 1963
5-20-63
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Solar Oil Company

Complete Address: 1117 Union Nat'l Bldg., Wichita, Kansas

Lease Name Garver Well No. 1

Location NW NW SE Sec. 28 Twp. 24 Rge. 5 (E) (W) X

County Reno Total Depth 3427'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: Lost Hole (lost circulation at TD)

Plugging Contractor: Harms Drilling Company

Address: Box 480, Great Bend, Kansas License No.

Operation Completed: Hour 3 AM Day 15 Month May Year 1963

The Above well was plugged as follows:

Fluid standing at 1800'. Rock bridge set from 1800' to 1770'. Approx.

5' of dry clay put on top of rock bridge to hole fluid. Hole filled

with mud to 490' Rock bridge set from 490' to 485'. Tried to fill

hole with mud but would not fill above 485'. (salt zone)

Pushed plug to 280'. Set rock bridge from 280' to 270' and cemented with

35 sacks cement through drill pipe. (top of cement 225') Filled hole

with mud to 30'. Pushed plug and 1/2 sack hulls to 30' and cemented hole

to base of cellar with 15 sacks. Rathole cemented with 5 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: L. J. Loman
Well Plugging Supervisor

DATE 5/21/63

INV. NO. 9113-U