

*M* KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

FEB 19 1965  
2-19-65  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Inger Oil Company

Complete Address: 1030 Central Bldg., Wichita, Kansas

Lease Name Mayhew Well No. # 4-B

Location NW SE NW Sec. 35 Twp. 25 Rge. 16 (E) (W)W

County Edwards Total Depth 4453'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 11:00AM Day 18th Month Feb. Year 1965

The Above well was plugged as follows:

399' of 8 5/8" surface pipe, cemented with 350 sacks. 4452' of 5 1/2" long string, cemented with the temperature survey at 3500'. Bottom of the hole was sanded to 4440', and cemented with 5 sacks. 2685' of 5 1/2" long string was recovered from the hole. Fluid in the hole was at 54'. Bridge plug was pushed in fluid to 300', and 10' rock bridge. 4 sacks of cement was mixed in barrel, and put on plug at 290', through the dump bailer, and let set over-night. Next morning hole was bailed dry and 21 sacks of cement was added to the plug. Hole was filled with mud to 40', and 10' of rock bridge, and 10 sacks of cement, bringing the cement to the base of cellar.

I hereby certify that the above well was plugged as herein stated.

DATE 2/19/65

INV. NO. 9704-W

Signed: Archie Elving  
Well Plugging Supervisor