

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 24 1967
4-24-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Well Plugging Authority,
issued April 3, 1967.

Operator's Full Name Wichita Iron & Metals Corp., Inc.

Complete Address: Box 13021, Wichita, Kansas

Lease Name Mayhew Well No. # 1

Location NE NE NW Sec. 35 Twp. 25 Rge. 16 (E) (W)W

County Edwards Total Depth 4410'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Glen & Smith Casing Pulling Company

Address: Box 156, Ellinwood, Kansas License No. 396

Operation Completed: Hour 10:30AM Day 19th Month April Year 1967

The Above well was plugged as follows:

388' of 8 5/8" surface pipe, cemented with 275 sacks. 4410' of 5 1/2" long
string, cemented with 125 sacks. Top perferation 3880'. Bottom of the hole
was sanded to 3860', and cemented with 5 sacks, through the dump bailer.
3400' of 5 1/2" long string was recovered from the hole. Bridge plug was pushed
in fluid to 300', bridge plug and rock bridge from 300' to 290'. 5 sacks of
cement was mixed in a barrel, and put on plug at 290', through the dump bail-
er, and let set over-night. Next day hole was bailed dry, and 20 sacks of
cement was added to the plug. Hole was filled with mud to 40', rock bridge
from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 4/24/67
INV. NO. 5103-W