

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
KANSAS CORPORATION COMMISSION
JAN 13 1967
1-13-67
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Southland Royalty
Complete Address: 1405 Wilco Bldg., Midland, Texas
Lease Name F. B. Lamb Well No. # 2
Location SW SW NE Sec. 36 Twp. 25 Rge. 16 (E) (W) W
County Edwards Total Depth 4465'
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: Southwest Casing Pulling Company
Address: Box 364, Great Bend, Kansas License No. 399
Operation Completed: Hour 11:30AM Day 11th Month Jan. Year 1967

The Above well was plugged as follows:

388' of 8 5/8" surface pipe, cement circulated/ 4465' of 5 1/2" long string,
cemented with 125 sacks. Plug back T.D. 4340'. Top perforation 4325'. Bottom
of the hole was sanded to 4300', and cemented with 5 sacks, through the dump
bailer. 3225' of 5 1/2" long string was recovered from the hole. Bridge plug was
pushed in fluid to 350', bridge plug and rock bridge from 350' to 340'. 3 sacks
of cement was mixed in a barrel, and put on plug at 340', through the dump
bailer, and let set over-night. Next day hole was bailed dry, and 22 sacks of
cement was added to the plug. Hole was filled with mud to 40', rock bridge
from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 1/13/67
INV. NO. 4599-W