

15-047-00292-00-01

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
MAY 5 - 1966
5-5-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Santa Fe Pipe & Supply, Inc.

Complete Address: P. O. Box 562, Great Bend, Kansas

Lease Name Hupp Well No. # 1

Location SW SW SE Sec. 17 Twp. 25 Rge. 17 (E) (W) W

County Edwards Total Depth 4650'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Santa Fe Pipe & Supply, Inc.

Address: P. O. Box 562, Great Bend, Kansas License No. _____

Operation Completed: Hour 10:30AM Day 4th Month May Year 1966

The Above well was plugged as follows:

245' of 8 5/8" surface pipe, cemented with 200 sacks. 4550' of 5 1/2" long string, cemented with 100 sacks. Top perforation 4463'. Bottom of the hole was sanded to 4450', and cemented with 5 sacks, through the dump bailer.

3927' of 5 1/2" long string was recovered from the hole. Bridge plug was pushed in fluid to 240', rock bridge from 240' to 230'. 7 sacks of cement was mixed in a barrel, and put on plug at 230', through the dump bailer, and let set over-night. Next day hole was bailed dry and 18 sacks of cement was added to the plug. Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 5/5/66

INV. NO. 3164-W