

KANSAS

FORM CP-3
Rev. 5-5-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-047-20,946-00-00

200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name Edwards Oil, Inc.

Complete Address 1215 E 30th, Box 206 Hutchinson Kans 67501

Lease Name Boguen Well No. 1

Location NW-NW-NW Sec. 23 Twp. 25S Rge. 17W (East) (West)

County Edwards Total Depth 4555'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Big Cat Drilling Co.

Address Box 18154 Wichita Kans 67202 License No. _____

Operation Completed: Hour: 8:30 PM Day: 17 Month: October Year: 19 81

Plugging Operations attended by Agent? All Part None

The above well was plugged as follows:

The anhydrite was topped at 1150'. There is 426' of 8 5/8" surface casing cement circulated. 1st plug after circulating heavy mud for 10 min, at 950' with 40 sbs cement. 2nd plug pushed rubber plug to 420' and pumped 35 sbs on top of it. 3rd plug with hole full of heavy mud, 40' to 0' with 10 sbs of cement on solid bridge. They put 5 sbs cement in rat hole & 5 sbs of cement put in water well. Plugging by Halliburton Co. out of Pratt Kans.

RECEIVED
STATE CORPORATION COMMISSION

I hereby certify that the above well was plugged as herein stated.

10-22-81
CONSERVATION DIVISION
Wichita, Kansas

DATE 11-1981

Signed: Paul Luther
Conservation Division Agent

NV. NO. 8333-W