

10 KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 20 1962
7-20-62
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Braden Drilling Co.

Complete Address: 1206 Un. Nat'l Bg. , Wichita, Kansas

Lease Name ~~Copperman~~ **GATTEMAN** Well No. 1

Location NE NE NW Sec. 34 Twp. 25 Rge. 17 (E) (W) X

County Edwards Total Depth 4670'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 304 , Chase, Kansas License No. 436

Operation Completed: Hour 3 p.m. Day 17 Month 7 Year 1962

The Above well was plugged as follows:

4548' of 5 1/2" pipe. Top perforation 4460'. Sanded to 4400' and 5
sacks cement. 277' of 8 5/8" surface pipe. Filled with mud to 250',
10' rock bridge and 20 sacks cement. Filled with mud to 40', 10' rock
bridge and 10 sacks cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7/20/62
INV. NO. 5410-W

Signed: Herman J. Justus
Well Plugging Supervisor