

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name Pickrell Drilling Co.

Complete Address 205 Litwin Bldg., Wichita, Ks. 67202

Lease Name Fatzer "B" Well No. 1

Location SE SE Sec. <sup>26</sup>16 Twp. 25s Rge. 17 (E)    (W) X

County Edwards Total Depth 4548

Abandoned Oil Well    Gas Well X Input Well    SWD Well    D & A   

Other well as hereafter indicated   

Plugging Contractor Kelso Casing Pulling.

Address Box 176 Chase, Ks. 67524 License No. 683

Operation Completed: Hour 11:15 Am. Day 2 Month 6 Year 1979

The above well was plugged as follows:

265' 85/8" casing w/225 sax cement. 4 1/2" casing set at 4546' w/150  
sax cement. Plug back to 4505'-Pref., at 4465'-Allied mixed & pumped 35  
sax common cement in 4 1/2" casing, release plug - Pump to 4230' w/3000#  
pressure. Pull 3910' 5 1/2" casing. Allied mixed & pumped 5 sax hulls-  
25 sax gel-Release plug-Pump 125 sax cement in 8 5/8" casing w/12% gel-  
3 % cc to top of casing. Shut in w/75# pressure.

STATE CORPORATION COMMISSION

JUN - 5 1979  
6-5-79

CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED

DATE 6-5-79

INV. NO. 9761-W