

15-047-20436-00-00

KANSAS

FORM CP-3  
Rev. 11-3-80

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

*Rec'd  
1-16-81*

API Number 15- -

245 North Water  
Wichita, KS 67202

Operator's Full Name North American Drilling & Exploration

Complete Address 3420 10th St., Great Bend, Kansas 67530

Lease Name Mellecker Well No. 1

Location NE NE Sec. 27 Twp. 25S Rge. 17 (~~18S~~) (West)

County ~~Stafford~~ Edwards Total Depth 4490'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Nicholas Casing Pulling

Address Box 373, Geneseo, Kansas 67444 License No. 711

Operation Completed: Hour: 11:15 AM Day: 15 Month: 1 Year: 19 81

The above well was plugged as follows:

Sanded back to 4450' and 5 sx cement with dump bailer.

Set 20' rock bridge at 350' and 4 1/2 yards of ready-mix  
cement to bottom of celler.

Recovered 2740' of 5 1/2" casing.

4482' of 5 1/2" casing cemented with 100 sx cement.

611' of 8 5/8" surface casing cement circ.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

DATE 2-18-81

INV. NO. 4503-w

Signed: *Dwight Rankin*  
Conservation Division Agent