

1 090123

10-2
API NUMBER 15-047-20,202-0000

7R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C SW NW, SEC. 20, T 25 S, R 16 W/E
3300 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5420

Lease Name Stapleton Well # 1

Operator: White & Ellis Drilling, Inc.
Name &

County Edwards 145.60

Address P.O. Box 48848
Wichita, KS 67201-8848

Well Total Depth 4480 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 324

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Pratt Well Service, Inc. License Number 5893

Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 3 p.m. Day: 2 Month: 10 Year: 19 91

Plugging proposal received from Bruce Wagner

(company name) Pratt Well Service, Inc. (phone) 316-672-2531

were: 4 1/2" at 4479' w/125 sx cement, PBTD 4390', Perfs at 4354-64'

1st plug sand back to 4300' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cemen.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3:40 p.m. Day: 2 Month: 10 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 4300' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 50 psi and shut in on vacuum.

RECEIVED
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2085' of 4 1/2" casing.

OCT 07 1991

(If additional description is necessary, use BACK of this form.)

INVOICED
Observe this plugging.

Signed 
(TECHNICIAN)

DATE 11-4-91

INV. NO. 33581