

1030306

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-047-20,741-0000

NE NE NE, SEC. 20, T 25 S, R 16 W/X
4950 feet from N SE Corner of
330 feet from W SE Corner of
XXX section line
XXX section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5141

Lease Name Brown Well # 1-6

Operator: Zenith Drilling Corporation
Name & Address 505 Fourth Financial Center
Wichita, KS 67202

County Edwards

Well Total Depth 4490 145.93 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 299

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 2:00 pm Day: 24 Month: October Year: 19 84

Plugging proposal received from Neil Peddicord

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" set at 4488' Perfs 4411-18

1st plug sand back to 4355' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump 125 sx cement.

Plugging Proposal Received by Steve Quinon (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 4:00 pm Day: 24 Month: October Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 4488' Perfs at 4411-18'

1st plug sanded back to 4355' and dumped 4 sx cement on top of sand through bailer,

2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

released 8 5/8" rubber plug and pumped an additional 125 sx cement.

Maximum pressure 200 psi and shut in pressure 50 psi

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Recovered 3500' of 4 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by Allied.
(If additional description is necessary, use BACK of this form.)

observe this plugging.

Signed Steve Quinon (TECHNICIAN)

DATE 11-7-84

INV. NO. 4698