

11-23

To: 1 120169
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 047-20,237-0000
C W/2 NW, SEC. 20, T 25 S, R 16 W/E

TECHNICIAN'S PLUGGING REPORT

3960 feet from S section line
4620 feet from E section line

Operator License # 5420

Lease Name Stapleton Well # 2

Operator: White & Ellis Drilling, Inc.
Name &
Address 401 East Douglas, Suite 500
Wichita, KS 67202

County Edwards 144.63

Well Total Depth 4450 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 332

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 10:30 a.m. Day: 23 Month: 11 Year: 19 88

Plugging proposal received from Jim Rockhold

(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 4 1/2" at 4449' PBTD 4410' Perfs at 4363-81' Elevation 2079' GL

1st plug pump 2 sx hulls, 25 sx common cement and plug,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 120 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

NOV 29 1988

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations Observed by Agent?: All Part _____ None _____

Operations Completed: Hour: 12 p.m. Day: 23 Month: 11 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug pumped in 4 1/2" casing with 100 lbs. hulls, 25 sx cement
with 100 lbs. hulls mixed in, pushed plug to 3400',

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 120 sx cement.

Pumping pressure 0-200 psi and shut in 0 psi (not on vacuum).

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2872' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

~~Observe this plugging.~~

DATE DEC 1 1988

Signed Deane Rankin
(TECHNICIAN)

INV. NO. 22222