

1-25-88

1050994

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-047-20,222-0000

SW, NE SE, SEC. 19, T 25 S, R 16 W/2  
1650 feet from S section line  
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5427

Lease Name Dora-Hoar Estate Well # 1

Operator: D.R. Lauck Oil Company, Inc.  
Name & Address 221 South Broadway, Suite 400  
Wichita, KS 67202

County Edwards 145.89  
Well Total Depth 4489 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 365

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 2 p.m. Day: 25 Month: 1 Year: 1988

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 4 1/2" at 4489' PBTD 4460' Perfs at 4420-30'

1st plug sand back to 4370' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 120 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3 p.m. Day: 25 Month: 1 Year: 1988

ACTUAL PLUGGING REPORT 1st plug sanded back to 4370' and dumped 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"

wiper plug and pumped 120 sx cement.

Maximum pressure 100 psi and shut in 25 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2220' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

INVOICED

Signed Richard W. Lacey (TECHNICIAN)

DATE 1-28-88

INV. NO. 19689

STATE CORPORATION COMMISSION  
JAN 27 1988  
CONSERVATION DIVISION  
Wichita, Kansas