

To: 1 060137  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

6-25 API NUMBER 15- 057-20,504-0000 147R

SW NW NE, SEC. 25, T. 25 S, R. 21 W/E  
4290 feet from S section line  
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5422  
Operator: Abercrombie Drilling, Inc.  
Name & Address 150 N. Main, Suite 801  
Wichita, KS 67202

Lease Name Valadez Well # 1  
County Ford  
Well Total Depth 4808 156.26 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 397

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Abercrombie RTD, Inc. License Number 30684  
Address 150 N. Main, Suite 801, Wichita, KS 67202

Company to plug at: Hour: 11:45 a.m. Day: 25 Month: 6 Year: 19 92

Plugging proposal received from Bill Craig

(company name) Abercrombie RTD, Inc. (phone) 316-262-1841

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1418'

1st plug at 1450' with 50 sx cement, 2nd plug at 725' with 80 sx cement,  
3rd plug at 430' with 50 sx cement, 4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement,  
6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Case Morris (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 2 p.m. Day: 25 Month: 6 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug at 1450' with 50 sx cement,  
2nd plug at 725' with 80 sx cement,  
3rd plug at 430' with 50 sx cement,  
4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement,  
6th plug to circulate mousehole with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 29 1992  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED (did not) observe this plugging.

DATE 7-16-92  
INV. NO. 35674

Signed Case Morris (TECHNICIAN)

EFFECTIVE DATE: 6-10-92

State of Kansas

057-20,504

NOTICE OF INTENTION TO DRILL

Must be approved by the K.C.C. five (5) days prior to commencing well--

DISTRICT 1  
YEAR 1992

Expected Spud Date 6 month 8 day 92 year

OPERATOR: License # 5422  
Abercrombie Drilling, Inc.  
Name: 150 N. Main, Suite 801  
Address: Wichita, KS 67202  
City/State/Zip: Jack L. Partridge  
Contact Person: 316-262-1841  
Phone:

CONTRACTOR: License #: 30684  
Name: Abercrombie RWD, Inc.

Well Drilled For: Well Class: Type Equipment:  
 Oil  Enh Rec  Infield  Mud Rotary  
 Gas  Storage  Pool Ext.  Air Rotary  
 Other  Disposal  Wildcat  Cable  
 Seismic;  # of Holes  Other  
If KNOWN old well information as follows:  
Operator: N/A  
Well Name:  
Comp. Date: N/A Old Total Depth

Directional, Deviated or Horizontal wellbore?  yes  no  
If yes, true vertical depth: N/A  
Bottom Hole Location:

Exp. 12/5/92

AFFIDAVIT

200' Alt. II Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-

Pusher Bill Craig  
SPUD DATE 6-16-92 INIT. R.C.  
LENGTH SURFACE PLANNED 360  
RESERVE PIT STATUS- REMOVE FLUID LINED  
after salt sect. bbls. when done bbls.  
RATHOLED AHEAD?  N SIZE HOLE  
SURFACE PIPE 2 3/4 @ 327 CONDUCTOR  
ANHYDRITE T- B-1418 ELEVATION  
TD 4808 FORMATION MISS  
RAN PIPE @ SX DV TOOL ALT II DONE  
SX Y N  
Arbuckle Plug @        Ft. W/ SX  
Hug./Council @        Ft. W/ SX  
Anhydrite Base @ 1450 Ft. W/ 50 SX  
1/2 Base Anyh. @ 725 Ft. W/ 80 SX  
1/2, 1/2 Plug @        Ft. W/ SX  
Bottom Surface @ 430 Ft. W/ 50 SX  
40' Plug @ 40 Ft. W/ 10 SX  
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX  
WATER WELL SX (Irr Well Pond       )  
TECHNICIAN CS DATE 6/29/92 Hauling         
TYPE OF CEMENT 60/40 RECEIVED STATE CORPORATION COMMISSION  
STARTING TIME 11:45 (AM/PM) DATE 6-25-92  
COMPLETION TIME 2:00 (AM/PM) DATE 6-25-92  
CEMENT COMPANY Allied

4290' feet from South / North line of Section  
2310' feet from East / West line of Section  
IS SECTION  REGULAR  IRREGULAR  
(NOTE: Locate well on the Section Plat on Reverse Side)  
County: Ford  
Lease Name: Valadez Well #: #1  
Field Name: unknown FORD  
Is this a Prestrat/Spaced Field?  yes  no  
Target formation(s): LKC, Cherokee, Miss  
Nearest lease or unit boundary: 330'  
Ground Surface Elevation: 992.284' feet MSL  
Water well within one-quarter mile:  yes  no  
Public water supply well within one mile:  yes  no  
Depth to bottom of fresh water: 185'  
Depth to bottom of usable water: 320' 550'  
Surface Pipe by Alternate: 1 2  
Length of Surface Pipe Planned to be set: 360'  
Length of Conductor pipe required: none  
Projected Total Depth: 4750'  
Formation at Total Depth: Miss  
Water Source for Drilling Operations:  well  farm pond  other  
DWR Permit #: Will file  
Will Core Be Taken?: N/A  yes  no  
If yes, proposed zone: