

To: 1 052212
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 207B
Wichita, KS 67202

12-22

API NUMBER 15-047-21,112-6000
NE SW SW, SEC. 24, T 26 S, R 16 W/EX
990 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 8061
Operator: Oil Producers, Inc. of Kansas
Name & Address: P.O. Box 8647
Wichita, KS 67208-8674

Lease Name Elledge Well # 1
County Edwards 147.88
Well Total Depth 4550 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 537

Abandoned Oil Well _____ Gas Well Input Well _____ SMO Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor D S & W Well Servicing, Inc. License Number 6901
Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 10 a.m. Day: 22 Month: 12 Year: 19 97

Plugging proposal received from Kent Strube
(company name) D S & W Well Servicing, Inc. (phone) 316-587-2341

logs: 4 1/2" at 4549' w/125 sx cement, Perfs at 4449-58'

1st plug sand back to 4400' and dump 4 sx cement on top of sand through bailer,
2nd plug at 1000' with 10 sx gel and 50 sx cement,
3rd plug at 550' with 50 sx cement,
4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 12:30 p.m. Day: 22 Month: 12 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 4400' and dumped 4 sx cement on top of sand through bailer,

Spotted plugs through casing:
2nd plug at 1000' with 10 sx gel and 50' sx cement,
3rd plug at 550' with 50 sx cement,
4th plug at 40' with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
JAN 5 1998
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2250' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

I (did / XXXXXX) observe this plugging.
DATE JAN 06 1998

INV. NO. 49830
12-22

Signed Richard M. Lacey (TECHNICIAN)