

1 070016.

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 047-21,264-0000

SW SW SW , SEC. 24 , T 26 S, R 16 W/8

330 feet from S section line

4950 feet from E section line

Lease Name Ellidge Well # 2

County Edwards

Well Total Depth 4552 14794 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 259

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061

Operator: Oil Producers, Inc. of Kansas

Name & Address P.O. Box 8647

Wichita, KS 67208

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor D S & W Well Servicing, Inc. License Number 6901

Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 11:15 a.m. Day: 11 Month: 4 Year: 19 96

Plugging proposal received from Kent Strube

(company name) D S & W Well Servicing, Inc. (phone) 316-587-3361

Notes: 4 1/2" at 4551' w/150 sx cement, PBD 4530', Perfs at 4490-4510'

1st plug sand back to 4450' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:55 a.m. Day: 11 Month: 4 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug sanded back to 4450' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,

released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 150 psi and shut in 25 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 800'-4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED (if additional description is necessary, use BACK of this form.) observe this plugging.

DATE APR 18 1996

REL. NO. 45359

Signed [Signature] (TECHNICIAN)

RECEIVED APR 15 1996