

11-29

API NUMBER 15- 047-21,303-0000

To: 1 120497
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

W/2 NW SW, SEC. 24, T 26 S, R 16 W/8
1980 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061
Operator: Oil Producers, Inc. of Kansas
Name & Address: Box 8647
Wichita, KS 67208

Lease Name Ellledge Well # 3
County Edwards 146.73
Well Total Depth 4515 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 266

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635
Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 10 a.m. Day: 29 Month: 11 Year: 19 90

Plugging proposal received from Gary Burke
(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 4 1/2" at 4514' w/125 sx cement, PBD 4500', Perfs at 4452-77'
1st plug sand back to 50' above perfs and dump 3 sx cement on top of sand through bailer,
2nd plug pump in 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 125 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:30 a.m. Day: 29 Month: 11 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 4400' and dumped 4 sx cement on top of sand through bailer,
2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.
Pumping pressure 0-200 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2210' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION

DEC 6 1990

INVOICED

DATE 12-10-90

INV. NO. 30205

Signed Duane Rankin (TECHNICIAN)

SEAL