

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-047 20,687-0000

SE4, Sec. 24, T26 S, R16 W/E  
(SESWSE) feet from N/S section line  
\_\_\_\_\_ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6724

Lease Name DOUGETT Well # 1

Operator: CINCO Exploration Company  
Name & Address 3935 HALESDALE  
HOUSTON, TX 77063

County EDWARDS  
Well Total Depth 4790 feet  
Conductor Pipe: Size 8 5/8 feet 319'  
Surface Casing: Size 5 1/2 feet 4780'

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor PRATT WELL SERVICE, INC License Number 5893  
Address Box 847, PRATT, KS 67124

Company to plug at: Hour: 10:4m Day: 6 Month: 11 Year: 1982

VERBAL PLUGGING ORDERS GIVEN TO GUS TRAWACK

(company name) CINCO (phone) \_\_\_\_\_

were: SAND BOTTOM TO 4450' AND PUT 5 SY. CEMENT ON  
TOP - USE 50/50 POZMIX, 470 gel - 3% C.C. and  
pump 4 hulls - 25 sy cmt - 25 sy gel - 1 sy hulla  
and release 8 5/8 plug followed by 125 sy cmt.

Signed R. Barbuton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 1:00 pm Day: 6 Month: 11 Year: 1982

ACTUAL PLUGGING REPORT

The well was plugged as requested.  
Rec'd 2250' of 4 1/2" casing  
Shut in pressure was 150 H

Remarks: PERFS TOP @ 4502'

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 15 1982  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated  
and that I (did / did not) observe this plugging.

Signed Steve Shumant  
(TECHNICIAN)

INVOICED  
DATE 12-20-82  
INV. NO. 1865-W

155, 158

11-11-11  
11-11-11  
11-11-11

11-11-11  
11-11-11  
11-11-11  
11-11-11