

1 120861

11-19

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 047-20,861-0000  
NE NW NE, SEC. 25, T 26 S, R 16 W/EX  
4950 feet from S section line  
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 8061  
Operator: Oil Producers, Inc. of Kansas  
Name & Address: P.O. Box 8647  
Wichita, KS 67208

Lease Name Salcer A Well # 1  
County Edwards  
Well Total Depth 4510 146.5 feet  
Conductor Pipe: Size 13 5/8 feet 127  
Surface Casing: Size 8 5/8 feet 411

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A   
Other well as hereinafter indicated

Plugging Contractor DS&W Well Servicing, Inc. License Number 6901  
Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 2 p.m. Day: 19 Month: 11 Year: 19 93  
Plugging proposal received from Joe

(company name) DS&W Well Servicing, Inc. (phone) 316-587-3361  
wells: 4 1/2" at 4509' w/150 sx cement, PBT 4486', Perfs at 4242-72'

1st plug sand back to 4200' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump in 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,  
100 lbs. hulls, release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None   
Operations Completed: Hour: 3:30 p.m. Day: 19 Month: 11 Year: 19 93

ACTUAL PLUGGING REPORT 1st sanded 4 1/2" casing back to 4190' and dumped 4 sx cement on top of  
sand through bailer,  
2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10  
sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.  
Maximum pressure 200 psi and shut in 50 psi.

Remarks Used 60/40 Pozmix 6% gel by Allied. Recovered 2500' of 4 1/2" casing. STATE CORPORATION COMMISSION  
(if additional description is necessary, use BACK of this form.)

RECEIVED

NOV 24 1993

Observe this plugging.

Signed [Signature] CONSERVATION DIVISION (TECHNICIAN) Wichita, Kansas

DATE 12-8-93  
INV. NO. 39419