

1030156

21026-0600

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 047-20,476  
NW NE NE, SEC. 26, T 26 S, R 16

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061

feet from N/S section line  
feet from W/E section line

Lease Name Wood "C" Well # 12

Operator: Oil Producers, Inc. of Kansas  
Name & Address P. O. Box 8647  
Wichita, KS 67208

County Edwards

Well Total Depth 4600 149.50 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 499

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 3:00 pm Day: 18 Month: April Year: 1984

Plugging proposal received from Bob Brenneman

(company name) Kelso (phone) 316-938-2457

were: 4 1/2 set at 4599' PBD 4500' Perf 4445

1st plug sand back to 4390' and dump 4 sx cement on top of sand

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

and release 8 5/8" rubber plug and pump an additional 150 sx cement

Maximum pressure 100# and shut in pressure 50#

Plugging Proposal Received by Steve Almonet (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 5:05 pm Day: 18 Month: April Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2 set at 4599' PBD 4500' Perf 4445'

1st plug sand back to 4390' and dump 4 sx cement on top of sand, 2nd plug squeeze well

with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, and release 8 5/8"

rubber plug and pump an additional 150 sx cement.

Maximum pressure 100# and shut in pressure 50#

Remarks: They recovered 3026' of 4 1/2" casing. Use 60/40 Pozmix 2% gel 3% cc by Allied  
(if additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED

STATE CORPORATION COMMISSION

DATE 4-20-84

APR 20 1984

Signed Steve Almonet (TECHNICIAN)

INV. NO. 1196 4-18

CONSERVATION DIVISION  
Wichita, Kansas

FORM CP-2/3  
Rev. 01-84