

1 040866

7-12

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-047-21,231 - ~~0000~~
110' S of C
E/2 SE NE, SEC. 26, T. 26 S, R. 16 W.X
3190 feet from S section line
330 feet from E section line
Lease Name Wood Well # 2
County Edwards
Well Total Depth 4580 148.85 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 385

TECHNICIAN'S PLUGGING REPORT

Operator License # 8061

Operator: Oil Producers, Inc. of Kansas
Name & Address P.O. Box 8647
Wichita, KS 67208

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor D.S. & W. Well Servicing, Inc. License Number 6901

Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 11:30 a.m. Day: 12 Month: 7 Year: 19 94

Plugging proposal received from Kevin Strube

(company name) D.S. & W. Well Servicing, Inc. (phone) 316-587-3361

logs: 4 1/2" at 4580' w/150 sx cement, PBSD 4557', Perfs at 4526-41, 4468-88'

1st plug sand back to 4415' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and dump 150 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:30 p.m. Day: 12 Month: 7 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug sanded back to 4415' and dumped 4 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 500 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2300' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED

(If additional description is necessary, use BACK of this form.) observe this plugging.

DATE 7-26-94

INV. NO. 40888

Signed Stephen J. Pfeifer (TECHNICIAN)

STATE CORPORATION COMMISSION
RECEIVED
JUL 15 1994
CONSERVATION DIVISION
Wichita, Kansas