

1 120331

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-047-20,738-0000

NE NW NE, SEC. 27, T 26 S, R 16 W/E  
4950 feet from S section line  
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5817

Lease Name Salser C Well # 1-27

Operator: Benson Mineral Group, Inc.

County Edwards 150.15

Name & Address 1536 Cole Blvd., Suite 220

Well Total Depth 4620 feet

Golden, CO 80401

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 438

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 3 p.m. Day: 26 Month: 10 Year: 19 89

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 4 1/2" at 4620' Perfs at 4433-4504' (3 sets)

1st plug sand back to 4380' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4:30 p.m. Day: 26 Month: 10 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 4380' and dumped 4 sx cement

on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Pumping pressure 0-200 psi and shut in 0 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2201' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

STAMP: STATE CORPORATION COMMISSION, CONSERVATION DIVISION, WICHITA, KANSAS, NOV 27 1989

INVOICED

DATE 11-2-89

Signed Steve Pfeifer (TECHNICIAN) 

INV. NO. 26296