

To: 1 051228  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

11-2  
API NUMBER 15-047-20,739-000  
SE SW NE, SEC. 27, T 26 S, R 16 W/E  
2970 feet from S section line  
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5817

Lease Name Wood D Well # 1-27

Operator: Benson Mineral Group, Inc.

County Edwards 150.80

Name &

Address 1536 Cole Blvd., Suite 220

Well Total Depth 4640 feet

Golden, CO 80401

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 420

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 2:30 p.m. Day: 2 Month: 11 Year: 19 89

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 4 1/2" at 4638' PBD 4699' Perfs at 4531-48'

1st plug sand back to 4480' and dump 4 sx cement on top of sand through bailer

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 1 sx hulls, 10 sx gel, release 8 5/8"

wiper plug and pump 125 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV - 6 1989  
CONSERVATION DIVISION  
WICHITA, KANSAS

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3:30 p.m. Day: 2 Month: 11 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 4480' and dumped 4 sx cement on top of sand through bailer.

2nd plug pumped down 8 5/8" with 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, released

8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 150 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2200' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

**INVOICED**  
I should observe this plugging.

DATE 11-13-89

Signed Richard W. Lacy  
(TECHNICIAN)

INV. NO. 26379