

To: 1020117
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

1-28-88 183
API NUMBER 15-047-21,304-0000
SW NW SE, SEC. 27, T 26 S, R 16 W/EX
1650 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5421
Operator: Sage Drilling Company, Inc.
Name & Address 202 South St. Francis
Wichita, KS 67202

Lease Name Giles A Well # 2
County Edwards 151.45
Well Total Depth 4660 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 500

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Duke Drilling Company, Inc. License Number 5929
Address Box 823, Great Bend, KS 67530

Company to plug at: Hour: 9:20 p.m. Day: 28 Month: 1 Year: 1988

Plugging proposal received from Leonard Williamson
(company name) Duke Drilling Company, Inc. (phone) 316-267-1331

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2079' KB
Anhydrite 1085'
1st plug at 1095' with 50 sx cement,
2nd plug at 530' with 40 sx cement,
3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 10 sx cement.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 11:10 p.m. Day: 28 Month: 1 Year: 1988

ACTUAL PLUGGING REPORT 1st plug at 1095' with 50 sx cement,
2nd plug at 530' with 40 sx cement,
3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
FEB 03 1988
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton.
(If additional description is necessary, use BACK of this form.)

INVOICED
Observe this plugging.

Signed Glenn P. Barlow
(TECHNICIAN)

DATE 2-4-88
INV. NO. 19730

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date December 15, 1987 month day year

API Number 15-047-21,304-0000

OPERATOR: License # 5421 Name Sage Drilling Co., Inc. Address 202 S. St. Francis City/State/Zip Wichita, Kansas 67202 Contact Person Casey Coats Phone 316/263-6139

SW NW SE Sec. 27 Twp. 26 S, Rg. 16 East 1650 Ft. from South Line of Section 2310 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side) Nearest lease or unit boundary line 990 feet County Edwards

CONTRACTOR: License # 5929 Name Duke Drilling Co., Inc. City/State Wichita, Kansas

Lease Name Giles A Well # 2 Ground surface elevation 2073 (est.) feet MSL Domestic well within 330 feet yes X no Municipal well within one mile yes X no

Well Drilled For: X Oil SWD Infield X Mud Rotary Gas Inj X Pool Est Air Rotary OWWO Expl Wildcat Cable

Depth to bottom of fresh water 200 Depth to bottom of usable water 450-300 Surface pipe by Alternate 1 X 2 Surface pipe planned to be set 500

If OWWO: old well info as follows: Operator Duke Drilling Co Bx 823 Well Name Great Bend KS Comp Date Old Total Depth 6750

Conductor pipe required None (But a 4 or 5' deep casing) Projected Total Depth 4700 Formation Cherokes, Kinderhook, Mississipp

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications. Date 1/19/87 Signature of Operator or Agent Charles Casey Coats Title Petroleum Engineer

For KCC Use: Conductor Pipe Required 320 feet Minimum Surface Pipe Required 320 feet per Alt. 1 X This Authorization Expires 5-20-88 Approved By RCH 11-20-87

EFFECTIVE DATE: 11-25-87 set 500' of 8 3/8 on 1-22-88

SW NW SE Sec. 27 Twp. 26 S, Rg. 16 East X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with columns for plug depth, size of material, and type of plug. Includes entries for 1st, 2nd, 3rd, 4th, and 5th plugs, and Rathole and Moushole.

Handwritten notes and signatures: PUSHER Leonard Williamson, TD 4660 FORMATION 8 3/8, SURFACE PIPE 500 @, ANHYDRITE 10 85 ELEVATION 2071, STARTING TIME & DATE 1-28-88 9:30 PM, COMPLETION TIME & DATE 1-28-88 11:00 PM, 1st PLUG @ 1095 FT. W/ 50 SX, 2nd PLUG @ 530 FT. W/ 40 SX, 3rd PLUG @ 40 FT. W/ 10 SX, 4th PLUG @ FT. W/ SX, RAT HOLE CIRCULATED W/ 10 SX, MOUSE HOLE CIRCULATED W/ SX, WATER WELL PLUGGED W/ SX, CEMENT COMPANY Halliburton, Technician Glen Barlow, 60/40 w/ 27-gal

RECEIVED STATE CORPORATION COMMISSION FEB 03 1988 CONSERVATION DIVISION Wichita, Kansas