

8-17-88

To: 1 030969
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 047-20,928-0000

NE SW NW, SEC. 4, T 26 S, R 16 W
3725 feet from S section line
4140 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3521
Operator: Ranger Petroleum Corporation
Name & Address: Box 1036
Wichita, KS 67201

Lease Name Shultz Well # 1
County Edwards 147.23
Well Total Depth 4530 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 452

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor: Pratt Well Service License Number 5893
Address: Box 847, Pratt, KS 67124

Company to plug at: Hour: 8 a.m. Day: 17 Month: 8 Year: 19 88

Plugging proposal received from John Luther

(company name) Pratt Well Service (phone) 816-672-2531

were: 5 1/2" at 4529' PBTD 4529' Perfs at 4442-7'

1st plug sand back to 4480' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 125 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
AUG 23 1988

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 9:30 a.m. Day: 17 Month: 8 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4480' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 400 psi and shut in 250 psi.

Remarks: Used 50/50 Pozmix 4% gel by B.J. Titan. Recovered 2460' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

(If desired) observe this plugging.

Signed Steve Durrant (TECHNICIAN)

DATE 8-24-88

INV. NO. 21906 8-17