

1 120140

10-3

15-047-20962-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- E-20,908

SE NW NE, SEC. 4, T 26 S, R 16 W/XX

4297 feet from S section line

1655 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5142

Lease Name Mayhew "A" Well # 7-4

Operator: Sterling Drilling Company

County Edwards 147.39

Name & Address Box 129

Well Total Depth 4535 feet

Sterling, KS 67579

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 430

Abandoned Oil Well Gas Well Input Well X SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 9 a.m. Day: 3 Month: 10 Year: 19 88

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 4 1/2" at 4526' Perfs at 4414-15, 4427-31'

1st plug sand back to 4385' and dump 4 sx cement on top of sand through bailer.

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 120 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
7 1988

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Commenced by Agent? Hour: 10 a.m. Day: 3 Month: 10 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4385' and dumped 4 sx cement on top of sand through bailer.

2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 120 sx cement.

Pumping pressure 0-400 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. Recovered 2300' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOLVED observe this plugging.

DATE 10-10-88

Signed [Signature] (TECHNICIAN)

INV. NO. 22566