

1051015

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 047-20,963-0000

SW NE NE, SEC. 4, T 26 S, R 16 W/E
4297 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5142

Lease Name Cudney "B" Well # 8-4

Operator: Sterling Drilling Company

County Edwards 147.39

Name & Address Box 129

Well Total Depth 4535 feet

Sterling, KS 67579

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 448

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 1 p.m. Day: 4 Month: 3 Year: 19 88

Plugging proposal received from Dallas Fulls

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 4525' PBTD 4500' Perfs at 4462-66'

1st plug sand back to 4410' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:15 p.m. Day: 4 Month: 3 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4410' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released

8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 400 psi and shut in 100 psi.

RECEIVED STATE CORPORATION COMMISSION

MAR - 9 1988

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2100' of 4 1/2" (If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION Wichita, Kansas

INVOICED

observe this plugging.

Signed Richard W. Lacey (TECHNICIAN)

DATE 3-10-88

INV. NO. 20069