

1040959 5-2

15-047-20974-00-00

API NUMBER ~~15-047-21,974-0000~~

STATE CORPORATION COMMISSION  
Wichita State Office Bldg. **PLUGGING SECTION**  
130 S. Market, Room 2078  
Wichita, KS 67202

Irreg. sec. SEC. 4, T 26 S, R 16 ~~W~~

1875 feet from ~~N~~ section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Lease Name Cudney B Well # 9

Operator: F.G. Holl Company L.L.C.

County Edwards 147.39

Name & Address P.O. Box 780167

Well Total Depth 4535 feet

Wichita, KS 67278-0167

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 433

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Pratt Well Service License Number 5893

Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 2:45 p.m. Day: 2 Month: 5 Year: 19 95

Plugging proposal received from Tom Pool

(company name) F.G. Holl Co. (phone) 316-995-3171

were: 4 1/2" at 4530' w/150 sx cement, PBTD 4498', Perfs at 4420-24'

1st plug sand back to 4350' and dump 4 sx cement on top of sand bridge through bailer.

2nd plug pump down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3:30 p.m. Day: 2 Month: 5 Year: 1995

ACTUAL PLUGGING REPORT 1st plug sanded back to 4350' and dumped 4 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement

Maximum pressure 400 psi and shut in 50 psi.

RECEIVED  
STATE CORPORATION COMMISSION

MAY 14 1995

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3093' of 4 1/2" casing  
(if additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION

**INVOICED**  
observe this plugging.

DATE 5-16-95

Signed Steve Pfeifer  
(TECHNICIAN)

INV. NO. 42834