

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5142

Operator: Sterling Drilling Company
Name & Address Box 129
Sterling, KS 67579

12-6

API NUMBER 15-047-20,975-0600
NW SE NE, SEC. 4, T 26 S, R 16 W ~~NE~~
3630 feet from S section line
990 feet from E section line
Lease Name Cudney "B" Well # 10-4
County Edwards 147.88
Well Total Depth 4550 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 441

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 12:30 p.m. Day: 6 Month: 12 Year: 1988

Plugging proposal received from Mark McCabe

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 4 1/2" at 4548' Perfs at 4440-44'

1st plug sand back to 4390' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 120 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

DEC 9 1988

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by _____? All Part _____ None _____

Operations Completed Wichita, Kansas 3:30 p.m. Day: 6 Month: 12 Year: 1988

ACTUAL PLUGGING REPORT 1st plug sanded back to 4390' and dumped 4 sx cement on top of
sand through bailer,

2nd plug pumped 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 120 sx
cement.

Maximum pressure 350 psi and shut in 150 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2341' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

Signed Paul Luthi
(TECHNICIAN)

INVOICED

DATE 12-12-88
INV. NO. 23327