

To: 1 120541  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

3-11  
API NUMBER 15- 047-20,989-0600 208R

SW SE NW, SEC. 4, T 26 S, R 16 W/E  
2970 feet from S section line  
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5142  
Operator: Sterling Drilling Company  
Name & Address P.O. Box 129  
Sterling, KS 67579

Lease Name Mayhew "A" Well # 9-4  
County Edwards 147.87  
Well Total Depth 4550 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 431

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SMD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050  
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11:30 a.m. Day: 11 Month: 3 Year: 19 91

Plugging proposal received from Millard Kelso  
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 4 1/2" at 4543.5' w/225 sx cement, Perfs at 4441-45'  
1st plug sand back to 4400' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"  
wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1 p.m. Day: 11 Month: 3 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 4390' and dumped 4 sx cement on  
top of sand through bailer,  
2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement,  
10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.  
Pumping pressure 0-300 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. Recovered 2424' of 4 1/2" casing. MAR 15 1991  
(If additional description is necessary, use BACK of this form.)

**INVOICED**  
I did not observe this plugging.

DATE 4-3-91  
INV. NO. 31316

Signed [Signature]  
(TECHNICIAN)