

1040956

4-26

API NUMBER 15-047-20,991-0000

STATE CORPORATION COMMISSION  
Wichita State Office Bldg. PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

Irr. Sec. SEC. 4, T 26 S, R 16 W/E

1216 feet from N & section line

1656 feet from W & section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Lease Name Cudney A Well # 8-4

Operator: F.G. Holl Company L.L.C.

County Edwards

Name: Address P.O. Box 780167

Well Total Depth 4575 148.69 feet

Wichita, KS 67278-0167

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 438

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Pratt Well Service License Number 5893

Address: P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 9:45 a.m. Day: 26 Month: 4 Year: 1995

Plugging proposal received from Kenny Gates

(company name) Pratt Well Service (phone) 316-672-2531

work: 4 1/2" at 4565' w/175 sx cement, PBDT 4546', Perfs at 4455-59'

1st plug sand back to 4405' and dump 4 sx cement on top of sand bridge through bailer,

2nd plug pump down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:15 a.m. Day: 26 Month: 4 Year: 1995

ACTUAL PLUGGING REPORT 1st plug sanded back to 4405' and dumped 4 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 400 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2340' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 5-2-95

INV. NO. 42726

Signed Steve Pfeifer (TECHNICIAN)

KANSAS CORPORATION COMMISSION  
RECEIVED  
MAY 01 1995  
CONSERVATION DIVISION  
WICHITA, KS