

1040955 4-26

STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 047-20,992-0060
Irr. Sec. SEC. 4 T 26 S, R 16 W/E
1216 feet from NS section line
990 feet from WE section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056
Operator: F.G. Holl Company L.L.C.
Name:
Address P.O. Box 780167
Wichita, KS 67278-0167

Lease Name Cudney A Well # 9
County Edwards
Well Total Depth 4560 148.20 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 432

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Pratt Well Service License Number 5893
Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 10:45 a.m. Day: 26 Month: 4 Year: 1995

Plugging proposal received from Kernv Gates
(company name) Pratt Well Service (phone) 316-672-2531

Work: 4 1/2" at 4553' w/175 sx cement, PBTD 4530', Perfs at 4464-68'
1st plug sand back to 4350' and dump 4 sx cement on top of sand bridge through bailer,
2nd plug pump down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:30 a.m. Day: 26 Month: 4 Year: 1995

ACTUAL PLUGGING REPORT 1st plug sanded back to 4350' and dumped 4 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 300 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2375' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 5-2-95
INV. NO. 42723

Signed *Stephen J. Pfeifer*
(TECHNICIAN)

KANSAS RECEIVED
CORPORATION COMMISSION
MAY 07 1995
CONSERVATION DIVISION
WICHITA, KS