

To: 1 121031 5-16
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION S/2
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 047-21,093-0000
SW SW NW, SEC. 4, T 26 S, R 16 W/E
2650 feet from S section line
4948 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5255
Operator: McGinness Oil Company
Name & Address: 150 N. Main, Ste. 1026
Wichita, KS 67202

Lease Name Julie Jones Well # 1
County Edwards 149.50
Well Total Depth 4600 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 429

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Hardtner Well Service License Number 30607

Address: 150 N. Main, Ste. 1026, Wichita, KS 67202

Company to plug at: Hour: 3 p.m. Day: 16 Month: 5 Year: 19 95

Plugging proposal received from Douglas McGinness

(company name) McGinness Oil Company (phone) 316-267-6065

were: 5 1/2" at 4599' w/150 sx cement, PBD 4577', Perfs at 4507-4515'
1st plug sand back to 4450' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:30 p.m. Day: 16 Month: 5 Year: 1995

ACTUAL PLUGGING REPORT 1st plug sanded back to 4450' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped in 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Pumping pressure 0-250 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1300' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE JUN 13 1995
INV. NO. 42957
5-16

Signed Deanne Rankin
(TECHNICIAN)
RECEIVED
STATE CORPORATION COMMISSION
MAY 19 1995
WICHITA, KANSAS