

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-10031-00-00
Spot: CSESUNE Sec/Twnshp/Rge: 33-26S-18W
330 feet from S Section Line, 1650 feet from E Section Line
Lease/Unit Name: BURTON C J Well Number: 1
County: EDWARDS Total Vertical Depth: 4888 feet

Operator License No.: 3273
Op Name: LOEB, HERMAN L.
Address: PO BOX 524
LAWRENCEVILLE, IL 62439

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.625 feet: 669 WITH 500 SX CMT
Production: Size 5.5 feet: 4864 WITH 200 SX CMT
Liner: Size _____ feet: \$158.86

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/31/2001 12:00 PM

Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION

Proposal Rcvd. from: ALAN VRATIL Company: CLARKE CORPORATION Phone: (316) 886-5665

Proposed Plugging Method: SET CIBP @ 4175 WITH 2 SX CMT ON TOP. PUMP DOWN 8 5/8" WITH 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 150 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 07/31/2001 1:35 PM

KCC Agent: RICHARD LACEY

Actual Plugging Report:

PBTD 4827'. PERFS AT 4225-33, 4230-42, 4699-4705'. SET CIBP @ 4175' WITH 2 SX CMT ON TOP OF PLUG. PUMPED DOWN 8 5/8" CASING WITH 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 100# HULLS - 150 SX CMT. MAXIMUM PRESSURE 700#. SHUT IN PRESSURE 300#.

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 03 2001

CONSERVATION DIVISION
INVOICED

DATE 8-3-01

IV. NO. 2002060681

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICES. RECOVERED 2900' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed

Richard M. Lacey

(TECHNICIAN)

AUG 02 2001

Form CP-2/3

MD