



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

9-January 1982

VERBAL PERMIT FORM (To be filed by Plugging Agent)

15-047-20986-0000

Dear Sir:

Mr. Doyle Folberts of D.R. Lock Oil Co. Inc. has this date requested permission to plug the following described well:

Operator's Full Name: D.R. Lock Oil Co. Inc.

Complete Address: 221 S. Broadway Suite 400, Wichita Kansas 67202

Lease Name: _____ Well No. D-1

Location: 1650' FSL - 290' FEL - SW 1/4 Sec. 29 Twp. 25S Rge. 16W (E) (W)

County: Edwards Total Depth: 4520'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereafter indicated: _____

Mr. Folberts was instructed to plug the well as follows:

There is 369' of 8 3/8" surface casing cement circulated. The Anhydrite was topped at 1089'. 1st plug on solid bridge at 900' with 40 lbs of cement. 2nd plug pushed rubber plug to 330' and pumped 35 lbs on top of it. 3rd plug 40' to 0' on solid bridge with 10 lbs of cement. They pumped 10 lbs of cement in rat hole & 3 lbs of cement in water well. The plugging was accomplished by Allied Security Co. Inc.

Very truly yours,

STATE CORPORATION COMMISSION

JAN 12 1982

Paul Luthi
Conservation Division Agent
CONSERVATION DIVISION
Wichita, Kansas