

State of Kansas



FORM CP-2

JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water

WICHITA, KANSAS 67202

December 5, 1980

### VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Morris Towns of Mustang Drilling, Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Mustang Drilling, Inc.

Complete Address: Box 1425, Great Bend, Kansas 67530

Lease Name: Gales Well No. 1

Location: C N E N E Sec. 6 Twp. 25 Rge. 16 (W)

County: Edwards Total Depth: 4550'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Towns was instructed to plug the well as follows:

8 5/8" - 400' - 350' sacks Common 29 gal - 3% catch. Fill hole with mud.  
Pump 50 sacks cement through drill pipe at 480'. Pump 30 sacks  
cement through drill pipe at 400'. Fill hole with mud to 40'  
Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks  
cement. Cement rat hole with 10 sacks cement.

Very truly yours,

DEC 11 1980  
CONSERVATION DIVISION  
Wichita, Kansas  
12-11-80

Arthur J. Larson  
Conservation Division Agent