



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202
6-2-82

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

15-047-20751-0000

Dear Sir:

Mr. Bill Fulls of Kelso Casing pulling has this date requested permission to plug the following described well:

Operator's Full Name: Oil Properties Co. Inc.

Complete Address: Box 335 Andover, Kans 67002

Lease Name: Dehauer Well No. 1

Location: C-NW-SE/4 Sec. 26 Twp. 26 Rge. 16 (E) (M)

County: Edwards Total Depth: 4616'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Fulls was instructed to plug the well as follows:

They had 423' of 8 5/8" surface casing cement circulated. They ran 4615' of 4 1/2" production pipe. They plugged back 4473' perforated from 4454' to 58'. Top of cement outside 4 1/2" was at 3824'. 1st plug cemented off bottom with 35 sbx of cement. 2nd plug pumped through 8 5/8" with 5 sbx hulls 25 sbx Jell + release rubber plug + 140 sbx of cement. They recovered _____ of 4 1/2" casing. The plugging was accomplished by Allied Cementing.

Very truly yours,

Paul A. Luthin
Conservation Division Agent

STATE OF KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado, Derby Bldg.
Wichita, Kansas 67202-1286

INVOICE and WELL PLUGGING AUTHORITY

June 16, 1982

INVOICE NUMBER: 448-W

TO: Oil Properties Co., Inc.
1346 N. Woodlawn
Box 8467
Wichita, KS. 67208

PAYABLE UPON RECEIPT

15-047-2071-0000

PLUGGING ASSESSMENT AS FOLLOWS:

Kelso Casing Pulling
Dehaven #1
C NW SE, Sec.26-26S-16W. \$15.02
Edwards
T.D. 4616'

NOTE: ~~We also need the following~~ before our file is completed:

- Well Plugging Record (CP-4)
- Well Log
- Well Plugging Application (CP-1)

WELL PLUGGING AUTHORITY

Gentlemen:

This is your authority to plug the above subject well in accordance with the rules and regulations of the state corporation commission.

This authority is void after ninety (90) days from the above date.



Administrator

Mr. Paul Luthi, Box 495, Minneapolis, Kansas 67111 of the above mentioned well.
is hereby assigned to supervise the plugging of the well.