



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

8-February 1982

### VERBAL PERMIT FORM (To be filed by Plugging Agent)

15-047-21007-0000

Dear Sir:

Mr. Sandra Proffitt of Sterling Drilling Co. has this date requested permission to plug the following described well:

Operator's Full Name: Sterling Drilling Co.

Complete Address: Box 129 Sterling Kansas 67579

Lease Name: Mayhew Well No. ~~4570~~ A10-40

Location: 1876' FNL-1650' FWL of NN 1/4 Sec. 4 Twp. 26 Rge. 16W (E) (W)

County: Edwards Total Depth: 4570'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Sandra Proffitt was instructed to plug the well as follows:

There is 423' of 8 1/2" surface casing cement circulated. The hydrate was at 1071'. 1st plug at 1020' with 50 Sbk of cement 2nd plug at 400' with 35 Sbk of cement. 3rd plug on solid body of shells & rubber plug with 10 Sbk of cement. Then circulated 10 Sbk of cement in rat hole. The cement used was common cement with 2% alk 3% CC.  
The plugging was accomplished by pumping cement through drill pipe, with hole full of heavy mud, with allied cement.  
When they pull pumpout of water well plug with 3 Sbk of cement.

Very truly yours,

Paul Lutter  
Conservation Division Agent

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 17 1982  
CONSERVATION DIVISION  
Wichita, Kansas