



JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-047-10128-0000

RECEIVED
STATE CORPORATION COMMISSION

DEC 14 1964
12-14-64
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. F. L. Copeland of Western Petroleum Co., Inc. has this date requested permission to plug the following described well:

Mr. Copeland guarantees payment of the plugging fee.

Operator's full Name: Western Petroleum Co., Inc.

Complete Address: Box 65, Great Bend, Kansas

Lease Name: Donovan Well No. # 1

Location: SW NW Sec. 24 Twp. 26 Rge. 18 (E) (W) W

County Edwards Total Depth 4795 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Copeland was instructed to plug the well as follows:

335' of 8 5/8" surface pipe, cement circulated with 300 sacks.
Fill hole with drilling mud to 300', 1st cementing plug, bridge
with hulls, and cement with 25 sacks. Fill hole with drilling
mud to 40', 2nd cementing plug, bridge with hulls, and cement
with 10 sacks to base cellar. Bridge and cement rat hole with
2 sacks.

Very truly yours,

Archie Elving