

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Edwards County. Sec. 25 Twp. 26 Rge. 16 (E) W (W)
Location as "NE/CNW&SW" or footage from lines G SE 1/4 SW 1/4
Lease Owner Mull Drilling Co.
Lease Name Spencer Well No. 1
Office Address 670 N. 4th. Natl Bank Bldg. Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 2-22 1960
Application for plugging filed 2-22 1960
Application for plugging approved 2-22 1960
Plugging commenced 9:00 A. M. 2-22 1960
Plugging completed 10:00 A. M. 2-22 1960
Reason for abandonment of well or producing formation No Pay

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4647 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole filled with drlg. mud to depth of 300ft. #1 plug pushed to this depth with drill pipe 1/2 sack hulls put on top of plug and 20 sacks put on top of hulls. # 2 plug pushed to depth of 30 ft. after filling hole to this depth with drlg. mud. 1/2 sack hulls put on top of plug and 10 sacks cement put on top of plug. This finished plugging hole. Rat hole bridged at 10 ft. and 2 sacks cement added. This plugged rat hole.

STATE CORPORATION COMMISSION
FEB 26 1960
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Co. Tools (If additional description is necessary, use BACK of this sheet)
Address 670 N. 4th. Natl Bank bldg. Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Joseph O. Butts (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Joseph O. Butts
(Address) _____

SUBSCRIBED AND SWORN TO before me this 23rd day of February, 1960

My commission expires January 28, 1961.

Ethel Zimmerman
Ethel Zimmerman Notary Public.



B

15-047-00228-0000

ROTARY DRILLERS LOG

COMPANY: Mull Drilling Co., Inc., Et Al
Wichita, Kansas

ROTARY DRILLING COMMENCED: 2/8/60

CONTRACTOR: Mull Drilling Co., Inc.
Wichita, Kansas

ROTARY DRILLING COMPLETED: 2/22/60

CASING RECORD: Set 872' of 8 5/8" csg.
w/600 sax cmt.
D & A

LOCATION: Elma Spencer #1
C SE/4 SW/4 25-26S-16W
Edwards County, Kansas

(Figures indicate bottom of formation - measurements from top of Rotary Bushing)

1140'	Anhydrite
1605'	Red Bed & Shale
2080'	Shale
2290'	Shale & Lime
2375'	Lime
3365'	Lime & Shale
3986'	Sandy Lime & Shale
4462'	Lime & Shale
4532'	Mississippi Chert
4548'	Shale, etc.
4592'	Kinderhook Sand
4623'	Shale
4647'	Viola Chert

RECEIVED
STATE CORPORATION COMMISSION
MAR 16 1960
CONSERVATION DIVISION
Wichita, Kansas
Total Depth

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

MULL DRILLING COMPANY, INC.

Joseph B. Brungardt, Jr.
Joseph B. Brungardt, Jr.

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Subscribed and sworn to before me this 3rd day of March, 1960.



Madge N. Miller
Madge N. Miller, Notary Public

My Commission Expires: February 24, 1964