

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1
660 Ft. from S Section Lin.
660 Ft. from E Section Lin.

LEASE OPERATOR VAL Energy, Inc. / Reach Group

SEC. 25 TWP. 26 RGE. 16W(E) or (W)

ADDRESS Box 322 Haysville, Ks. 67060

COUNTY Edwards

PHONE (316) 522-1560 OPERATORS LICENSE NO. 5822

Date Well Completed 1985

Character of Well oil/gas

Plugging Commenced 7-31-92

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 8-4-92

The plugging proposal was approved on 7-31-92 (date)

by Dodge City, Ks. (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? N/A

Producing Formation Miss. Depth to Top 4425 Bottom 4490 D. 4470

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	water	0	449	8 5/8	449	none
	water	0	4575	4 1/2	4575	2214

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other pl were used, state the character of same and depth placed, from feet to feet each s
Sand back to 4300 ft. spot 4 sx cement. Pull pipe to 1000 ft pump
50 sx plug, pull up to 450 spot 50 sx plug, pull to 40 ft from surface
and circulate to surface. Allied Cementing 60/40 Pox 4% gel

Name of Plugging Contractor VAL Energy, Inc. License No. 5822

Address Box 322 Haysville, Ks. 67060

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: VAL Energy, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

K. Todd Allam (Employee of Operator) or (Operator)
above-described well, being first duly sworn on oath, says: That I have knowledge of the fac
statements, and matters herein contained and the log of the above-described well as filed t
the same are true and correct, so help me God.

(Signature) K. Todd Allam

(Address) Wichita, Ks.


SUBSCRIBED AND SWORN TO before me this 5th day of August, 19 92

Harry D. Stearns
Notary Public

RECEIVED
STATE CORPORATION COMMISSION

USE ONLY ONE SIDE OF EACH FORM

My Commission Expires:



AUG 6 1992
Form CP
Revised 05-
CONSERVATION DIVISION
Wichita, Kansas