

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Bldg.  
 Wichita, Kansas 67202

Form CP-4  
 Rev. 12-15-80

15-047-20476-0000

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Edwards SEC. 26 TWP. 26S RGE. 16W E/W  
 Location as in quarters or footage from lines:  
C N/2 NE/4


Locate Well  
 correctly on above  
 Section Platt.

Lease Owner Oil Properties Company, Inc.  
 Lease Name Woods C-1 Well No. \_\_\_\_\_  
 Office Address 403 W. Central Box 335 Andover, Ks. 67002  
 Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
 Date Well Completed \_\_\_\_\_  
 Application for plugging filed \_\_\_\_\_  
 Plugging commenced 6-3-82  
 Plugging completed 6-10-82  
 Reason for abandonment of well or producing formation \_\_\_\_\_

Depleted  
 Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Luthi  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4580'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	414'	none
				4-1/2"	4579'	2726'

Describe in detail the manner in which the well was plugged, indicating where the mud  
 fluid was placed and the method or methods used in introducing it into the hold. If cement  
 or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
 to \_\_\_\_\_ feet for each plug set.

Pumped 35 sacks cement on bottom, pushed bottom plug to 4500'. Shot casing @3840'.  
 3320', 3005', 2925', 2840' and 2725'. Pulled a total of 69 joints of 4-1/2" casing.  
 Plugged well with 5 sacks hulls, 25 sacks gel, 8-5/8" plug, 140 sacks 50/50 pos,  
 2% gel, 3% cc.

RECEIVED  
 STATE CORPORATION COMMISSION  
 JUN 4 7 1982

Plugging Complete.

CONSERVATION DIVISION  
 Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
 Name of Plugging Contractor Kelso Casing Pulling


STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the  
 facts, statements, and matters herein contained and the log of the above-described well as  
 filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
Box 347 Chase, Ks. 67524  
 (Address)

SUBSCRIBED AND SWORN TO before me this 15th day of June, 19 82

My Commission expires:



Irene Hoover  
 Notary Public.

Phone 913-483-2627, Russell, Kansas  
 Phone 316-793-5861, Great Bend, Kansas

15-847-20476-0000

Phone Plainville 913-434-2812  
 Phone Kiowa 316-825-4618

# ALLIED CEMENTING CO., INC.

No 29885

Home Office P. O. Box 31

Russell, Kansas 67665

Date	6/10/82	Sec.	26	Twp.	26	Range	16	Called Out		On Location	1:30 PM	Job Start		Finish	
Lease	WOODS	Well No.	C-1			Location	TROUPDALE 25 30 35 NW			County	EDWARDS	State	KS		

Contractor	KELSO CASING PULLING	
Type Job	PLUG TO ABANDON	
Hole Size	7 7/8	T.D.
Csg. Size	8 5/8	Depth
Tbg. Size		Depth
Drill Pipe		Depth
Tool		Depth
Cement Left in Csg.		Shoe Joint
Press Max.		Minimum
Meas Line		Displace
Perf.		

Owner	To Allied Cementing Co., Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.	
Charge To	OIL PROPERTY INC CO.	
Street	BOX 8647	
City	WICHITA	State KS 67202
The above was done to satisfaction and supervision of owner agent or contractor.		

Purchase Order No.	X Bill Zullb @ Kelso Casing
<b>CEMENT</b>	

Amount Ordered	140 5x 50/50 POZ 3% CC 2% GEL
----------------	-------------------------------

EQUIPMENT		
No	Cementer	
Pumptrk 105	Helper	JERRY PHIL
Pumptrk	Helper	
Bulktrk 101	Driver	VERL
Bulktrk 122	Driver	KEMMY

Consisting of	
Common	705x 4.25
Poz. Mix	705x 1.85
Gel.	285x 6.25
Chloride	45x 20.00
Quickset	
NULLS - 55x	14.00

DEPTH of Job		
Reference:	PUMP TRUCK	340.00
	57 mi @ 1.00 mi	
	8 5/8 PLUG	10.00
	Sub Total	
	Tax	
	Total	

Handling	1775x	904
Mileage	57 mi	664
	Sub Total	
	Total	

Remarks:  
 MIXED 55x NULLS / 255x GEL / RELEASED PLUG / 1405x CEMENT / SNUT-IN AT #.

Floating Equipment

Phone 913-483-2627, Russell, Kansas  
 Phone 316-793-5861, Great Bend, Kansas

Phone Plainville 913-434-2812  
 Phone Kiowa 316-825-4618

# ALLIED CEMENTING CO., INC.

Home Office P. O. Box 31

Russell, Kansas 67665

No 28130

Date	6-3-82	Sec.	26	Twp.	26	Range	16	Called Out		On Location	147 211' 30" 5m	Job Start	12:00m	Finish	
Lease	Woods	Well No.	C-1	Location				Trinidad 1/2s 35 35 1/2w Edwards	County	Edwards	State	Ks			

Contractor	Kobco Coaming	
Type Job	Plug off Bottom	
Hole Size	7 7/8	T.D. 4580
Csg. Size	4 1/2	Depth 4579
Tbg. Size		Depth
Drill Pipe		Depth
Tool		Depth
Cement Left in Csg.		Shoe Joint
Press Max.	1000*	Minimum
Meas Line		Displace
Perf.		

Owner	To Allied Cementing Co., Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.
Charge To	Oil Property Trust Co
Street	Box 8647
City	Wichita State K54
The above was done to satisfaction and supervision of owner agent or contractor.	
Purchase Order No.	
X	Bill Zull @ Kobco Coaming

**CEMENT**

EQUIPMENT		
No	Cementer	Weighted
Pumptrk 80	Helper	29000
No	Cementer	
Pumptrk	Helper	
101	Driver	WPA 1
Bulktrk		Lorry
Bulktrk	Driver	

Amount Ordered	355.50
Consisting of	
Common	185x 4.75 85.50
Poz. Mix	175x 1.85 31.45
Gel.	
Chloride	
Quickset	

DEPTH of Job		
Reference:	Pumptrk	450.00
	Plug	23.50
	Sub Total	
	Tax	
	Total	473.50

Handling	35.00	.90	31.50
Mileage	57 miles	.66	55.30
	Sub Total		
	Total		203.75
Floating Equipment			

Remarks:  
 mixed 35% released plug pumped to 4300'