

15-04700231-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

OR

FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging of formations.

Edwards

County. Sec. 27 Twp. 26 Rge. (E) 16 (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. NE C SE 1/4

Lease Owner. Herndon Drilling Company

Lease Name. LONG Well No. 1

Office Address. P. O. Box 1836, Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed. October 10 19 42

Application for plugging filed. 19

Application for plugging approved. November 10 19 42

Plugging commenced. November 11 19 42

Plugging completed. November 15 19 42

Reason for abandonment of well or producing formation.

If a producing well is abandoned, date of last production. 19

Was permission obtained from the Conservation Division or its agents before plugging was com-
menced?

Name of Conservation Agent who supervised plugging of this well. C. T. Alexander, Wichita, Kansas

Producing formation. Depth to top. Bottom. Total Depth of Well. 4918 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8	828	None
				5-1/2	4722'	3502

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole filled with mud to 828 / Cement plug - 20' at 828. Hole filled with mud to 10' of surface / cement to surface

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Herndon Drilling Company,
Address. P. O. Box 1836, Tulsa, Oklahoma

STATE OF Oklahoma COUNTY OF Tulsa, ss.
SETH W. HERNDON

(employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) SETH W. HERNDON
President of Herndon Drilling Company

SUBSCRIBED AND SWORN TO before me this 27th day of May, 1947

My commission expires Sept. 19, 1948

(Address)
Notary Public:


PLUGGING
FILE SEC 27 T 26 R 16W
BOOK PAGE 55 LINE 33

ate spudded: September 13, 1942
 Date set casings: Sept. 18, 1942 (8-5/8")
 Date completed: October 10, 1942

Loc: 27-26-16
 Edwards County, Kansas
 Herndon

Total depth: 4918'

<u>From</u>	<u>To</u>	<u>Formation</u>	<u>Remarks</u>
0	11	Top bushing to cellar	
11	150	Surface soil and sand	
150	440	Red bed and shale	
440	840	Sand and red bed	
840	948	Red rock and sand	
948	1081	Shale and shells	
1081	1090	Anhydrite	
1090	1100	Anhydrite	
1100	1595	Shale and shells	
1595	1785	Shale and shells	
1785	1885	Broken lime	
1885	2135	Shale and lime shells	
2135	2240	Shale and shells	
2240	2350	Shale and shells and sand	
2350	2500	Shale and lime	
2500	2660	Shale and sandy lime	
2660	2685	Lime	
2685	2735	Lime sandy	
2735	2810	Lime sandy	
2810	2945	Broken lime	
2945	3065	Broken lime	
3065	3190	Broken lime	
3190	3265	Lime	
3265	3355	Lime	
3355	3435	Lime	
3435	3525	Lime	
3525	3625	Lime	
3625	3695	Lime	
3695	3815	Lime	
3815	3880	Lime	
3880	3901	Shale and sand	
3901	3960	Shale	
3960	3982	Shale	
3982	4010	Lime	
4010	4045	Lime	
4045	4050	Lime and chert	
4050	4085	Lime	
4085	4135	Lime	
4135	4180	Lime	
4180	4245	Lime	
4245	4290	Lime	
4290	4325	Lime	
4325	4350	Lime and shale	
4350	4400	Shale and lime	
4400	4450	Lime and shale	
4450	4463	Shale and lime	
4463	4490	Sandy shale with stks of chert	
4490	4495	Shale	
4495	4535	Chert	
4535	4549	Chert and lime	
4549	4565	Sand	
4565	4575	Sand and shale	
4575	4590	Sand and shale	
4590	4605	Chert	
4605	4635	Chert and shale	
4635	4644	Chert and shale	
4644	4670	Lime and chert	
4670	4690	Lime and chert	
4690	4735	Lime and chert	
4735	4770	Lime and chert	
4770	4805	Shale and sand	
4805	4820	Shale and lime	
4820	4838	Shale	
4838	4855	Lime	
4855	4910	Lime	
4910	4918	Lime	



Sub. No. 107
 COMMISSIONER

HERNAN BARTIG

PLUGGING
 FILE SEC 27-26-16 W
 BOOK PAGE 52 LINE 33

hereby certify the foregoing to be true and correct copies of the original
 Miller's log on the B. J. Long #1.

Chester J. Moore (over)

I hereby certify the foregoing to be true and correct copies of the original.

Subscribed and sworn to before me this 29th. day of May, 1947.

John W. Ryan
Notary Public

My commission expires
Sept. 19, 1948