

mail to State

API NUMBER 15-047-21403-6000

LEASE NAME WOOD H

WELL NUMBER #1

2970 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 27 TWP. 26 RGE. 16 (E) or (W)

COUNTY Edwards

Date Well Completed 11-23-94

Plugging Commenced 2:30 AM

Plugging Completed 4:30 AM

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR OIL PRODUCERS, INC. OF KANSAS

ADDRESS P. O. BOX 8647

PHONE (316) 681-0231 OPERATORS LICENSE NO. 8061

Character of Well D & A

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-21-94 (date)

by Glen Barlow (KCC District Agent's Name).

Is AGO-1 filled? _____ If not, is well log attached? YES

Producing Formation _____ Depth to Top _____ Bottom _____ T.O. 4575'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	311'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, - from ___ feet to ___ feet each set

Plugged as follows: Heavy mud to 1320' with 50 sacks, heavy mud to 340' with 50 sacks, heavy mud to 40' with 10 sacks to surface and 15 sacks in rathole.

Name of Plugging Contractor STERLING DRILLING COMPANY License No. 5142

Address P. O. BOX 129, STERLING, KS 67579

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: OIL PRODUCERS, INC. OF KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.

Richard L. Mead, Vice President (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well and the same are true and correct, so help me God.



(Signature) Richard L. Mead

(Address) P. O. Box 129, Sterling, KS

SUBSCRIBED AND SWORN TO before me this 23rd day of November

Cheryl R. Davis
 Notary Public

RECEIVED
 STATE CORPORATION COMMISSION
 0500 8 1994
 CITY DIVISION
 WICHITA, KANSAS

My Commission Expires: 02-15-97

USE ONLY ONE SIDE OF EACH FORM

STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

(316) 278-2131

SAMPLE LOG ----- WOOD H#1

Located: 2970' FSL 2970' FEL SE SE NW Sec. 27-26S-16W,
Edwards County, Kansas

OWNER: OIL PRODUCERS, INC. OF KANSAS

ROTARY DRILLING CONTRACTOR: STERLING DRILLING COMPANY

COMMENCED: November 17, 1994

COMPLETED: November 23, 1994

TOTAL DEPTH: 4575' Driller

LOG

0' - 190' Surface Soil and Sand
190' - 314' Sand and Shale
314' - 715' Red Bed, Clay and Shale
715' - 1850' Shale
1850' - 4575' Lime and Shale

CASING RECORD

Spud at 1:30 PM, 11-17-94. Drilled 314' of 12 1/4" hole. Ran 8 joints 8 5/8" surface casing. 299.08' set at 311' K.B. Cemented with 180 sacks 60/40 Pozmix with 2% gel and 3% cc. Plug down at 6:15 PM by Allied, ticket #1001. Good returns.

Plugged.

DEVIATION SURVEY

1½° @ 4575'

RECEIVED
STATE CORPORATION COMMISSION

DEC 08 1994

CORPORATION DIVISION
WICHITA, KANSAS